



## SUPPLEMENTAL BID BULLETIN

### TO: ALL PROSPECTIVE BIDDERS

This Supplemental Bid Bulletin is issued to amend **Section VII**—Technical Specifications of the bid document published on January 22, 2025 under **PhilGEPS Reference No. 11680378**, for **Lot No. 1**—Procurement of 1 Lot Contract Package: Equipment, Labor and Materials for the Installation of 3-Phase Electrification for Rice Processing System II (RPS 2), Brgy. Capungagan, Kapalong, DDN (RE-BID) for the following details, viz;

FROM	TO
<p>PART II - OTHER GENERAL REQUIREMENTS B.3(1) – Permits and Clearances: 1.00 L.S. B.5 - Project Billboard/Signboard: 1.00 each B.7(1) - Occupational Safety and Health: 1.00 L.S. B.9 - Mobilization/Demobilization: 1.00 Lot</p> <p>PART III – CIVIL, MECHANICAL, ELECTRICAL AND SANITARY/PLUMBING WORKS</p> <p>PART A- EARTHWORK 803(1)a – Structure Excavation, Common Soil: 63.10 cu.m 804(2)a – Embankment, from Borrow: 32.80 cu.m 804(7) – Gravel fill: 9.84 cu.m</p> <p>PART B – PLAIN AND REINFORCED CONCRETE WORKS 900(1)c – Structural Concrete (3000psi, 28days): 42.89 cu.m 902(1) – Reinforcing Steel (Deformed): 7205.58 kgs. 903(2) – Formworks and Falseworks: 195.06 sq.m</p> <p>PART C – FINISHING AND OTHER CIVIL WORKS 1046(1)a1 – 100mm CHB Load Bearing (including Reinforcing Steel), 500psi : 65.00 sq.m 1027(1) – Cement Plaster Finish, 20mm thk. : 130.00 sq.m 1047(7) - Structural Steel: 547.64 kgs. 1720(5) - Metal Frames and Gratings/Cover: 1.00 L.S. 1722(1)c - Fence, Cyclone/Welded Wire: 62.78 sq.m. 1032(1)a - Painting Works, Masonry: 130.00 sq.m. 1032(1)c - Painting Works, Metal: 143.88 sq.m.</p> <p>PART D - ELECTRICAL WORKS 1100(10) - Conduits, Boxes &amp; Fittings (Conduit Works/Conduit Rough-in): 1.00 L.S. 1101(33) - Wires and Wiring Devices: 1.00 L.S. 1102(1) - Panel Board with Main and Branch Breakers: 1.00 L.S. 1103(1) - Lighting Fixtures and Lamps: 1.00 L.S. 1103(9) - Pad Mounted Transformer (OISC) with Complete Accessories: 1.00 L.S. 1111(1) - Reinforced Concrete Pedestal/Pole: 1.00 L.S. SPL(1) - Power Bill Deposit: 1.00 L.S.</p>	<p>PART II - OTHER GENERAL REQUIREMENTS B.3(1) – Permits and Clearances: 1.00 L.S. B.5 - Project Billboard/Signboard: 1.00 each B.7(1) - Occupational Safety and Health: 1.00 L.S. B.9 - Mobilization/Demobilization: 1.00 Lot</p> <p>PART III – CIVIL, MECHANICAL, ELECTRICAL AND SANITARY/PLUMBING WORKS</p> <p><b>(Part A, B &amp; C) (Transformer’s Pad w/ Gen. Set Pad (A= 94 sq.m.) and Cable Trench (L= 50.13m)</b></p> <p>803(1)a – Structure Excavation, Common Soil: 63.10 cu.m 804(2)a – Embankment, from Borrow: 32.80 cu.m 804(7) – Gravel fill: 9.84 cu.m</p> <p>PART B – PLAIN AND REINFORCED CONCRETE WORKS 900(1)c – Structural Concrete (3000psi, 28days): 42.89 cu.m 902(1) – Reinforcing Steel (Deformed): 7205.58 kgs. 903(2) – Formworks and Falseworks: 195.06 sq.m</p> <p>PART C – FINISHING AND OTHER CIVIL WORKS 1046(1)a1 – 100mm CHB Load Bearing (including Reinforcing Steel), 500psi : 65.00 sq.m 1027(1) – Cement Plaster Finish, 20mm thk. : 130.00 sq.m 1047(7) - Structural Steel: 547.64 kgs. 1720(5) - Metal Frames and Gratings/Cover: 1.00 L.S. 1722(1)c - Fence, Cyclone/Welded Wire: 62.78 sq.m. 1032(1)a - Painting Works, Masonry: 130.00 sq.m. 1032(1)c - Painting Works, Metal: 143.88 sq.m.</p> <p>PART D - ELECTRICAL WORKS 1100(10) - Conduits, Boxes &amp; Fittings (Conduit Works/Conduit Rough-in): 1.00 L.S. 1101(33) - Wires and Wiring Devices: 1.00 L.S. 1102(1) - Panel Board with Main and Branch Breakers: 1.00 L.S. 1103(1) - Lighting Fixtures and Lamps: 1.00 L.S. 1103(9) - Pad Mounted Transformer (OISC) with Complete Accessories <b>(3-167KVA D.B. Distribution- Type, Oil Immersed Pad Mounted, 13.2/7.6-240/120V, 125KV Bil, 60Cycles/sec, ONAN): 1.00 L.S.</b> 1111(1) - Reinforced Concrete Pedestal/Pole: 1.00 L.S. SPL(1) - Power Bill Deposit: 1.00 L.S.</p>

For guidance and information of all concerned.

Issued this 6<sup>th</sup> day of February, 2025.

  
**ATTY. RALPH P. DELA CRUZ, LT. COL., PA (RET)**  
Provincial Administrator  
BAC Chairperson

